



ALL INDIA INSTITUTE OF MEDICAL SCIENCES, PATNA

Office of the Superintending Engineer

Maintenance Cell, AIIMS Patna

PHULWARISHARIF, PATNA -801507

Phone No. 0612-2451114, Email - ee@aiimspatna.org

AIIMS/Pat/Q/EE(C)/2021-22/10

July, 2021


NOTICE INVITING QUOTATION No. 10

On behalf of Director AIIMS Patna, sealed quotations are invited by the Executive Engineer (Civil), AIIMS Patna on item rate basis for the below noted items supply/works which will be received at drop box placed at office of Superintending Engineer, Medical College Building, AIIMS Patna, from Agencies by 3:30 PM on or before 02.08.2021 and the same shall be opened on 02.08.2021 at 4:00PM in presence of quotationer or their authorised representative who like to be present. Intended contractor /agencies is required to download BOQ/NIQ from the website of AIIMS Patna WWW.aiimspatna.org and fillup quotation shall be dropped in the tender box of the engineering department. Engineer in-charge reserve the right assigning any reason whatsoever for cancellation of NIQ and quotation, they must have G.S.T No. and registered with government/ semi government department of state or central.

Name of Work	:	Provision of window grill ,raw water supply connection at HVAC Plant and replacement of shutter & fixing of 80mm GI pipe with suitable support for delivery of rain water pipe near HVAC plant, medical college block, at Aiims patna Campus.
Estimated Value of work	:	₹1,75,402/-
Period of Completion	:	20 days
Quotation opening Date	:	02/08/2021 At 04:00PM


Encl:

1. Terms & Conditions attached.
2. BOQ attached


B.K. Singh
Executive Engineer (Civil)
Aiims Patna

Terms & Conditions

1. The rates are to be quoted in words and figures including all taxes, (Including GST) transportation etc.
2. Document relating to registration of firm i.e. GST and relevant document should be submitted along with quotation.
3. The work shall be executed as per CPWD specification and direction of the Engineer-in-Charge.
4. **PAYMENT TERMS:-**Payment shall be released after the successful completion of the work and receipt of bill after deducting TDS as per Income tax Rules and any other deductions as per Government rules.the entire work shall have to be completed within the stipulated period.
5. Payment shall be made through Electronic Clearing System only and the charges shall be deducted from the bill.
6. Tenderers may please note that they shall follow the safety and security procedures while at work in AIIMS as per the Institute's norms.
7. Tenderers may please note that the work should be executed as per the standard CPWD specification and the measurements shall be recorded as per CPWD specification.
8. The work shall be carried out as per standard specifications of CPWD relevant IS code if the CPWD specification are silent and also as per manufacturers specifications as directed by Engineer-In-Charge.
9. If the contractor fails to maintain the required progress or to complete the work and clear the site on or before the expiry of contract period he shall on account of such breach, pay agreed compensation at ½% of the value of the work per week subject to maximum of 10% of tendered value of work.
10. Work should be completed within 20(Twenty) days from the date of issue of work order.
11. Performance guarantee @ 3% in the form DD/RTGS/NEFT in the favour of AIIMS Patna shall be submitted by L1 vendor before issuing of work order.
12. In case the agency is not started the work within 15 days of issue of the work order then the entire amount of Performance guarantee shall be forfeited by AIIMS Patna without any prior notice.
13. Quotation Name/ No. and due date of opening must be mentioned on top of envelopes.
14. AIIMS Patna reserve the right to accept or reject any or all quotations without assigning any reason there of and also does not bind itself to accept the lowest quotation. AIIMS Patna also reserves the rights to accept all the item in the given NIQ or only part of it in any given schedule without assigning any reason.
15. No labour below the age of fourteen year shall be employed on the work.
16. Wages of labour shall be paid as per contract labour regulation and abolition act.



B K Singh
Executive Engineer (Civil)
Aiiims Patna

BOQ

Name of work- Provision of window grill ,raw water supply connection at HVAC Plant and replacement of shutter & fixing of 80mm GI pipe with suitable support for delivery of rain water pipe near HVAC plant, medical college block, at AiiMS patna Campus.

Sl.No	Sub-heads and Item of work	Qty	Rate (Rs)	Unit	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge.				
	All kinds of soil.	0.1		cum	
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :				
	1:3:6 (1 Cement : 3 coarse sand (zone-III): 6 graded stone aggregate 40 mm nominal size)	0.10		cum	
3	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required.				
	In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works	630.00		kg	
4	Providing & fixing glass panes with putty and glazing clips in steel doors, windows, clerestory windows, all complete with :				
	4.0 mm thick glass panes	14.80		sqm	
5	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade :				
	Two or more coats on new work	74.10		sqm	
6	Applying priming coat:				
	With ready mixed red oxide zinc chromate primer of approved brand and manufacture on steel galvanised iron/ steel works	25.50		sqm	
7	Providing and fixing G.I. pipes complete with G.I. fittings including trenching and refilling etc.				
	80 mm dia nominal bore	10.00		metre	
8	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge.				
	20 mm nominal outer dia Pipes	30.00		metre	

9	Providing and fixing PTMT stop cock of approved quality and colour.				
	20 mm nominal bore, 89 mm long, weighing not less than 88 gms	1.00		each	
10	Making connection of G.I. distribution branch with G.I. main of following sizes by providing and fixing tee, including cutting and threading the pipe etc. complete :				
	25 to 40 mm nominal bore	1.00		each	
11	Providing and fixing PTMT bib cock of approved quality and colour.				
	15mm nominal bore, 86 mm long, weighing not less than 88 gms	1.00		each	
12	Supplying and fixing rolling shutters of approved make, made of required size M.S. laths, interlocked together through their entire length and jointed together at the end by end locks, mounted on specially designed pipe shaft with brackets, side guides and arrangements for inside and outside locking with push and pull operation complete, including the cost of providing and fixing necessary 27.5 cm long wire springs manufactured from high tensile steel wire of adequate strength conforming to IS: 4454 - part 1 and M.S. top cover of required thickness for rolling shutters.				
	80x0.90 mm M.S. laths with 0.90 mm thick top cover	10.20		sqm	
Total Quoted Amount					


 B. K. Singh
 Executive Engineer (Civil)
 Aiims Patna