ALL INDIA INSTITUTE OF MEDICAL SCIENCES, PATNA
Office of the Superintending Engineer
Maintenance Cell, AIIMS Patna
PHULWARISHARIF, PATNA -801507
Phone No. 0612-2451114, Email – ae.civil@aiimspatna.org

AIIMS/Pat/Q/EE(C)/2021-22/02 May, 2021

NOTICE INVITING QUOTATIONNo. 02

On behalf of Director AIIMS Patna, sealed quotations are invited by the Executive Engineer (Civil), AIIMS Patna on item rate basis for the below noted items supply/works which will be received at this office of Superintending Engineer, Medical College Building, AIIMS Patna, from Civil Contractor / Agencies by 3:30 PM on or before 21.05.2021 and the same shall be opened on 22.05.2021 at 10:00AM in presence of quotationer or their authorised representative who like to be present. Engineer in-charge reserve the right assigning any reason whatsoever, they must have G.S.T No.

Name of Work	:	**Provision of steps and pathway infront of post office and bank at AIIMS Patna**
Estimated Value of work	:	**₹44,463/-**
Period of Completion	:	**15 days**
Quotation opening Date		**22/ 05/2021 At 10:00AM**

Encl:

1. **Terms & Conditions attached.**
2. **BOQ attached**

Assistant Engineer (Civil)
Aiims Patna

18/5/21

Executive Engineer (Civil)
Aiims Patna

.....

...2/-

ALL INDIA INSTITUTE OF MEDICAL SCIENCES, PATNA
OFFICE OF THE SUPERINTENDING ENGINEER
PHULWARISHARIF, PATNA -801507
Phone No. 0612-2451114, Email: eeaiimspatna@gmail.com

BOQ					
N/W	**Name of work- Provision of steps and pathway in front of post office and bank at aiims patna**				
SLNo	**Description**	**Qty**	**Rate (Rs.)**	**Unit**	**Amount (Rs.)**
1	Earth work in surface excavation not exceeding 30 cm in depth but exceeding 1.5 m in width as well as 10 sqm on plan including getting out and disposal of excavated earth upto 50 m and lift upto 1.5 m, as directed by Engineer-in- harge:dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the xcavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.				
	All kinds of soil	20.00		sqm	
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :				
	1:5:10 (1 cement : 5 coarse sand (zone-III): 10 graded stone aggregate 40 mm nominal size)	1.62		cum	
3	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in:				
	Cement mortar 1:6 (1 cement : 6 coarse sand)	1.50		cum	
4	Chequerred precast cement concrete tiles 22 mm thick in footpath & courtyard, jointed with neat cement slurry mixed with pigment to match the shade of tiles, including rubbing and cleaning etc. complete, on 20 mm thick bed of cement mortar 1:4 (1 cement: 4 coarse sand).				
	Light shade pigment using white cement	20.00		sqm	
Total amount including GST					

Terms &Conditions

1. The rates are to be quoted in words and figures including all taxes, (Including GST) transportation etc.
2. Document relating to registration of firm i.e. GST and relevant document should be submitted along with quotation.
3. The work shall be executed as per CPWD specification and direction of the Engineer-in-Charge.
4. **PAYMENT TERMS:-**Payment shall be released after the successful completion of the work and receipt of bill after deducting TDS as per Income tax Rules and any other deductions as per Government rules.the entire work shall have to be completed within the stipulated period.
5. Payment shall be made through Electronic Clearing System only and the charges shall be deducted from the bill.
6. Tenderers may please note that they shall follow the safety and security procedures while at work in AIIMS as per the Institute's norms.
7. Tenderers may please note that the work should be executed as per the standard CPWD specification and the measurements shall be recorded as per CPWD specification.
8. The work shall be carried our as per standard specifications of CPWD relevant IS code if the CPWD specification are silent and also as per manufacturers specifications as directed by Engineer-In-Charge.
9. If the contractor fails to maintain the required progress or to complete the work and clear the site on or before the expiry of contract period he shall on account of such breach, pay agreed compensation at ½% of the value of the work per week subject to maximum of 10% of tendered value of work.
10. Work should be completed within 15(fifteen) days from the date of issue of work order.
11. Performance guarantee @ 3% in the form DD/RTGS/NEFT in the favour of AIIMS Patna shall be submitted by L1 vendor before issuing of work order.
12. 5% security deposit will be withheld and shall be released after completion of warranty D.L.P period.
13. In case the agency is not started the work within 15 days of issue of the work order then the entire amount of Performance guarantee shall be forfeited by AIIMS Patna without any prior notice.
14. 6 months warranty period from the date of virtual completion of the satisfactory installation or good's.
15. Quotation Name/ No. and due date of opening must be mentioned on top of envelops.
16. AIIMS Patna reserve the right to accept or reject any or all quotations without assigning any reason there of and also does not bind itself to accept the lowest quotation. AIIMS Patna also reserves the rights to accept all the item in the given NIQ or only part of it in any given schedule without assigning any reason.
17. No labour below the age of fourteen year shall be employed on the work.
18. Wages of labour shall be paid as per contract labour regulation and abolition act.
19. Defect liability period will be 6 month after recording at completion certificates.

Executive Engineer (Civil)
Aiims Patna